

2833

ROSCOMMON COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF ROSCOMMON

MAY 3 11 21 AM '94

For corners in

| | | |
|---------------------------------------|-------------|---------------|
| Roscommon (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T22N R3W | E-6 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | leg # 2 pm |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE Nov. 30, 1993 M.E.M.

TO BE FILED IN LIBER 3 OF LAND CORNE.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Larry L. Cavanagh, in a field survey on November, 1993,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|-----------------------------------|------------------------------------|--|
| W/post placed by Wm A. Burt 1849 | 1972 L. Cavanagh Sec survey Sec 16 | 1979 Deerwood Village L-7, P-31 |
| Aspen 6" N78°E 12 | Boat spike in MSHD Pav't Box | 1957 MDOI plans apparent same location |
| Aspen 9" S30°W 18 | Street sign S40°W 48.1 | Also older plan & undated) |
| 1940-present Numerous surveys | Power Pole S40°E 38.4 | |
| 1940 Houghton Beach Sub L-2, P-33 | 1977 L. Cavanagh land survey | |
| 1946 Robert T. Ostling sec survey | Boat spike in MSHD Pav't box | |
| 1/2"x18" bar | Street sign S40°W 48.1 | |
| Spike in Aspen 12" S45°E 69.8 | Power pole S40°E 38.4 | |
| Spike in Aspen 12" S25 1/2°W 75.3 | Spike in W side of P.P. N10°E 31.4 | |
| | No parking sign post N50°W 49.45 | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat spike in Monument Box 1.5' North of centerline of M-55, and is accepted as the best evidence
of the position of the original corner.

See filed dossier for detail of report.

SURVEY &
REMONUMENTATION

MAY 24 1995


COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Roscommon Co. Std. Mon in West edge of Pav't box stamped G-6 17614
N5 1/2°E Nail & tag in I. pole 31.45
S43°E Nail & tag in P. pole 39.23
S15°E Nail & tag in P. pole 106.57
S36°W Nail & tag in Denton Twp Cemetery sign post 48.64



THIS CERTIFICATE IS FILED TO CORRECT CERTIFICATE PREVIOUSLY FILED IN LIBER 3
PAGE 18 OF CORNERS. THE WITNESSES WERE PREVIOUSLY INTERCHANGED WITH
G-6.



Signed by [Signature] Date 4/26/94
Surveyor's Michigan License No. 17614
Date November 30, 1993 Peer Group Approved

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983