

ROSCOMMON COUNTY SURVEY &
PEER GROUP APPROVAL MONUMENTATION

DATE _____ LAND CORNER RECORDATION CERTIFICATE
Requirements of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

For corners in

Roscommon Located in _____ Corner Code # _____
(County)

22 NOV 94 11:09 A.M.

1. Public Land Survey T 23N R 3W G - 8
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

ROBERT W. SMITH
REGISTER OF DEEDS
ROSCOMMON COUNTY
PEER GROUP APPROVAL
DATE 10-20-94 M.E.M.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on October 14, 19 94,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Artemas Curtis 1852
Mon-Set Post
WIT: 8" Cedar S64°W 31 lks.
14" Aspen N45°E 39 lks.

Henning L.265, pg.444 6-72
Mon-1½" Pipe
WIT: 8" Hemlock S48°E 31.00'
12" Hemlock N19½°E 35.00'

Henning 8-44
Mon-placed 1½"x5' Pipe & Cedar Post
WIT: Mkd. B.T. 8" Hemlock S48°E 31.00'
Mkd. B.T. 12" Hemlock N19½°E 35.00'


Larry Cavanagh L.338, pg.565 10-19-77
Mon-1½" Pipe in cor.
WIT: 8" Hemlock S48°E 31.00'
12" Hemlock N19½°E 35.00'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument 1½" x 42" Pipe and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Standard Roscommon County Monument stamped "T23N R3W G-8 31600"
WIT: Set Wit. Tag & Nail SW side 11" Hemlock N12°W 10.00'
Set Wit. Tag & Nail N. side 12" Poplar N89°W 31.72'
Set Wit. Tag & Nail E. side 12" Poplar S09°W 39.41'
Set Wit. Tag & Nail S. side 19" Maple S88°E 61.59'
Set Carsonite Post S06°W 3'±



Signed by Marvin E. Myers

Date Nov 9, 1994

Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 178