

LAND CORNER RECORDATION CERTIFICATE **Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Roscommon

(County)

Located In:

Corner Code #

STATE OF MICHIGAN
 ROSCOMMON COUNTY
 RECORDED

28 APR 99 11:50 A.M.

ROBERT W. SMITH
 REGISTER OF DEEDS

1. Public Land Survey

T 24N R 4WB-7

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

I, Marvin E. Myers, in a field survey on March, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. - 1852

Addison P. Brewer D.S.

Mon. - Post

15" Y. Pine N4°E 15 lks.

28" Y. Pine S14°W 28 lks

Marcus Schaaf

June 1945

Mon: Iron Set

Found 1/4 cor Secs. 18 & 19 in center of fire line road East and center Fire line North, Iron set level with surface.

Wit: Found SW BT in place, NE falls in fire lane

22" White pine S35 1/2°E 90 lks

23" White Pine Stump N46°W 77 lks

28" White Pine Bottom S34°W 76 lks

16" White Pine N69°E 156 lks

Jerry L. Wilcox P.S. #14102

August 1980

Mon: Found 2" Iron Pipe in concrete in centerline of trails North and East,

Probable GLO stump to SW in place at Bearing and distance.

Wit: 16" Maple S55°E 24.04'

18" W. Pine N12°E 52.27'

6" Maple of twin N34°W 31.10

2" Red Pine S15°E 29.73'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" x 24" pipe in concrete of record in the intersection of the centerline of a fire lane North and a trail road East.

Found White Pine Stump S35 1/2°E 59.4' (90 links). Found 6" Twin Maple (now 8") N34°W 31.10. Found White Pine Stump N46°W 50.82' (77 links). Found 18" White Pine (now 24") N12°E 52.27'. Found 24" White Pine N69°E 102.96' (156 links). Found 16" Maple (now 18") S55°E 24.04'. Accepted pipe as a perpetuation of the Original Government Corner. Replaced pipe with Standard Roscommon County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard Roscommon County Corner 0.5' below surface.

Wit: Set nail & tag above overgrown spike in 18" Maple S55°E 23.91'


Set nail & tag above overgrown spike in 8" Twin Maple N34°W 31.13'

Set nail & tag above overgrown spike in 24" White Pine N12°E 52.34'

Set nail & tag in 8" Oak N58°E 77.77'


Set Carsonite Post South 15'±

Signed by


Surveyor's Michigan License No. 31600

ROSCOMMON COUNTY

PEER GROUP APPROVAL

DATE April 19, 1999


Marvin E. Myers, P.S.
 County Surveyor

Date April 20, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1985

LIBER 3 PAGE 569