

ST. CLAIR COUNTY, MICHIGAN  
OFFICIAL GOVERNMENT CORNER



LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Corner Code #  
7N 14E L-13

1. Public Land Survey T R  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Seg. 2

RECEIVED  
1995 AUG -4 AM 10:11  
REGISTER OF DEEDS  
ST. CLAIR COUNTY  
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat  
5. Private Claims

Daniel E. Johnson May 22, 95

I, in a field survey on , 19 , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 1 corner, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:

LIBER 007 PAGE 327

STATE PLAIN COORDINATES


N. \_\_\_\_\_

E. \_\_\_\_\_

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LIBER 007 PAGE 327

ELEVATION \_\_\_\_\_



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" Dia. Aluminum Cap inscribed "St. Clair County Official Corner" with magnet over Iron Rod R.L.S. #5557.

9.78' ESE to set P.K. and County Tag in 12" Apple (F.Dup.Sp.Below)  
24.70' S to set P.K. and County Tag in 15" Apple (F.Dup.Sp.Below)  
18.3' W to set P.K. and County Tag in 15" Apple (F.Dup.Sp.Below)  
25.85' N to set P.K. and County Tag in 15" Oak  
F. CCM #15405 ENE 1.3'

Signed by Daniel E. Johnson  
Daniel E. Johnson

Date May 22, 1995

Surveyor's Michigan License No. 13754

PA 345-1990  
PEER COMMITTEE

APPROVED AS AN OFFICIAL GOVERNMENT CORNER BY ST. CLAIR COUNTY:

Signed By: Daniel E. Johnson  
St. Clair County Land Surveyor Daniel E. Johnson  
13754

7-31-95  
Date

Surveyor's Michigan License No.

LIBER 008 PAGE 105

APPROVED 5-20-94 Dan