

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 15W	E6
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 16 T 43N R 15W	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on E6 02/14/2012
10 03/20/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16-17. 1973 - F.J.Bray RLS reestablished the corner position
midway and on line between Section corners 1/2 mile north and south. Set 1"ID I.pipe with 4" alum.
cap. 16" R.Pine N01E 25.8', 17" R.Pine S12W 26.0'.

(10-Sec. 16) South 1/16 corner between Sections 16 and 17. 1973 - Established by F.J.Bray RLS midway
and on line between Section and Quarter corners. Set 1"ID iron pipe with 4" alum. cap. 8" Spruce
S79W 24.3', 7" Spruce S12E 14.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) Found the 1973 monument in good condition and at record bearing and distance from the 1973
witnesses, both in good condition. Accepted the monument as a careful and faithful reestablishment
of the position of the original corner.

(10-Sec. 16) Found the 1973 monument in good condition and at record bearing and distance from the
1973 witnesses, now both stumps. Accepted the monument as a careful and faithful establishment of the
position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Fd. 1"ID I.pipe with 4" alum. MI Dept. of
Conservation cap.
Set measuring nail with MDNR tag in the side of:
18" R.Pine S17W 26.45' mrkd "1/4S" 1973 NBT
20" R.Pine N04E 26.5' do do
12" W.Pine S06E 25.85' "1/4S NBT"
10" W.Pine S69W 26.85' do
Bearings are magnetic.

(10) Fd. 1"ID I.pipe with 4" alum. MI Dept. of
Conservation cap.
Set measuring nail with MDNR tag in the side of:
7" Cedar S72W 21.95' mrkd "S1/16 BT"
12" Cedar N43W 27.3' do
8" Cedar N60E 17.85' do
5" Cedar S29E 16.5' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/06/2012

For the Michigan Department of Natural Resources, Forest Resources Division

