

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 15W T 43N R 15W T _____ R _____	G6 G5 _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	_____ _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on G6 02/13/2012
G5 03/14/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G6) Quarter corner common to Sections 15-16. 1973 - F.J.Bray RLS reestablished the corner position
midway and on the Section line between Section corners 1/2 mile north and south. Set 1"ID I.pipe
with 4" alum. cap. 8" J.Pine N46E 23.3', 8" J.Pine S42E 24.1'.

(G5) Corner common to Sections 9-10-15-16. 1972 - F.J.Bray RLS reestablished the corner position by
double proportionate measurement between corners 1 mile north, east and west, and 2 miles south. Set
1"ID iron pipe with 4" alum. cap. 12" J.Pine N01W 11.0', 10" J.Pine S80E 17.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G6) Found the 1973 monument in good condition. The 1973 witnesses were not recovered. Verified the
position of the corner with respect to Section corners north and south and accepted same as a careful
and faithful reestablishment of the position of the original corner.

(G5) Found the 1972 monument in good condition and at record bearing and distance from the 1972
witnesses. The J.Pine NW is a stump, the J.Pine SE is standing dead. Accepted the monument as a
careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G6) Fd. 1"ID I.pipe with 4" alum. MI Dept. of
Conservation cap.
Set measuring nail with MDNR tag in the side of:
10" J.Pine N33E 22.85' mrkd "1/4S NBT"
6" J.Pine S56W 17.0' do
7" J.Pine S43E 19.55' do
7" J.Pine S75E 40.55' do
Bearings are magnetic.

(G5) Fd. 1"ID I.pipe with 4" alum. MI Dept. of
Conservation cap.
Set measuring nail with MDNR tag in the side of:
10" R.Pine N87E 8.95' mrkd "S10 NBT"
8" W.Pine S31E 26.5' "S15 NBT"
10" J.Pine S56W 28.6' "S16 NBT"
12" W.Pine N65W 21.15' "S9 NBT"
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/06/2012

For the Michigan Department of Natural Resources, Forest Resources Division

