

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 15W T 43N R 15W T T	I5 G2
2. Property Controlling in Section	S S S S	T T T T
3. Miscellaneous Property in Sec.	S S	T T
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/14/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I5) Corner common to Sections 10-11-14-15. 1972 - Reestablished by double proportionate measurement by F.J.Bray RLS. Set 1" iron pipe with 4" alum. cap. 22" R.Pine N73°E 29.8', 9" R.Pine N41°W 4.3'.

(G2) Quarter corner common to Sections 3 and 4. 1972 - F.J.Bray RLS reestablished the corner position by single proportionate measurement to the original record between Section corners to north and south. Set 1" iron pipe with 4" alum. cap. 18" W.Pine N65°E 66.2', 9" W.Pine N04°E 66.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I5) Found the 1972 monument in good condition and at record bearing and distance from the 1972 witnesses. The R.Pine NE is a stump, the R.Pine NW is standing dead. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(G2) Found the 1972 monument in good condition and at record bearing and distance from the 1972 witnesses, now both cut stumps. The monument is substantially at the record position and I accept same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I5) Found 1" ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
12" W.Pine S49°W 15.7' mrkd "S15 NBT"  
12" R.Pine N86°W 47.8' "S10 NBT"  
13" W.Pine North 47.6' do  
5" W.Pine N44°E 29.6' "S11 NBT"  
E= 8065128.901 N= 149907.389

(G2) Found 1" ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
5" W.Pine N18°E 13.75' mrkd "1/4S NBT"  
6" W.Pine S36°E 20.0' do  
12" twin Maple S61°W 32.35' do  
7" W.Spruce N80°W 45.65' do  
E= 8063494.379 N= 152303.986

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)  
Coord. Ref.=NGS PID DL6164: N= 131822.939 m. E= 8059239.498 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/25/2013

For the Michigan Department of Natural Resources, Forest Resources Division

