

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S 15 T 43N R 15W S 15 T 43N R 15W S _____ T _____ R _____	6 9 _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/17/13 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(6-Sec. 15) Northeast 1/16 corner, Section 15. Not previously monumented.

(9-Sec. 15) East 1/16 corner, Section 15. Found no record of prior monumentation.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(6-Sec. 15) Established the position for the corner at the intersection of 1/16 lines. 1/16 corner  
#2, previously monumented in 1972 by F.J.Bray RLS, was discovered to be in an erroneous position and  
was not used to control the position of this corner.

(9-Sec. 15) Established the position for the corner midway and on a straight line between Quarter  
corner 1320.90' east and the intersection of 1/4 lines of Section 15 1320.90' west. From the  
position thus established I found a 1" iron pipe S38°E 4.9' distant which I did not accept as  
marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx32" I.pipe with 4" MI Dept. of  
Conservation cap (the monument which had been  
previously installed by F.J.Bray at 1/16 corner #2)  
Set measuring nail with MDNR tag in the side of:  
10" Sugar S62°W 24.1' mrkd "NE1/16 BT"  
5" Maple S19°E 10.95' do  
14" Maple N70°E 9.5' do  
14" Maple N03°E 17.1' do  
Set 4" sq'd pine post adjacent.  
E= 8064731.911 N= 149495.583

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
10" Maple N54°W 12.65' mrkd "E1/16 BT"  
7" Maple S07°W 26.9' do  
14" Hemlock N84°E 22.0' do  
Found 1"ID I.pipe S38°E 4.9'  
Set 4" sq'd pine post adjacent.  
E= 8064737.477 N= 149091.375

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID DL6164: N= 131822.939 m. E= 8059239.498 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/25/2013

For the Michigan Department of Natural Resources, Forest Resources Division

