

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 15 T 43N R 15W	7
	S 15 T 43N R 15W	14
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/26/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 15) North 1/16 corner between Sections 14 and 15. 1972 - Established by F.J.Bray RLS midway and on line between Section and Quarter corners. Set 1"ID I.pipe with 4" alum. cap. 6" Spruce N59°E 27.8', 14" W.Pine S56°E 45.0'.

(14-Sec. 15) South 1/16 corner between Sections 14 and 15. 1972 - Established by F.J.Bray RLS midway and on line between Section and Quarter corners. Set 1"ID I.pipe with 4" alum. cap. 6" R.Maple N64°E 9.9', 7" R.Maple S59°W 20.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7) Found the 1972 monument in good condition and at record bearing and distance from the remains of the 1965 witnesses, now both stumps. The position of the monument is substantially at the record position and I accept same as a careful and faithful establishment of the position of the corner.

(14) Found the 1972 monument in good condition and substantially at the record position. The 1972 witnesses were not recovered and their remains may have been obscured by deep snow. Accepted the position of the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
5" W.Pine S46°E 50.8' mrkd "N1/16 BT"  
8" R.Pine N13°E 59.2' do  
10" W.Pine S73°W 34.75' do  
6" R.Pine N61°W 25.0' do  
Sq'd pine post adjacent.  
E= 8065134.320 N= 149503.138

(14) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
9" Sugar S66°W 20.0' mrkd "S1/16 BT"  
10" Sugar N32°W 22.5' do  
18" Hemlock N60°E 58.55' do  
10" Maple S34°E 41.55' do  
E= 8065145.768 N= 148694.379

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)  
Coord. Ref.=NGS PID DL6164: N= 131822.939 m. E= 8059239.498 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/25/2013

For the Michigan Department of Natural Resources, Forest Resources Division

