

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 11/12/97

SURVEY &
REMONUMENTATION

JAN 21 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey

T42NR16W

T43NR16W

J-1

J-13

2. Property Controlling
in Section

S

T

R

S

T

R

3. Miscellaneous
Property in Sec.

S

T

R

S

T

R

Received & Filed this 9 day of
Dec. 1997 at 3:55 PM

Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Thomas P. O'Brien, in a field survey on Nov. 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1 N 1/4 Corner Section 2
June 3, 1841 - William A Burt D.S. set qr. section post.
Cedar 6 N70E 22 do 12 N62W 13

August 9, 1967 - Frank J. Bray R.L.S. placed corner "at old wood post with point of older post along side. Signature tree has Slater's name and is dated 9/3/31. Several trees with old blazes facing corner."
LCRC recorded Liber 3, page 175.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Nov. 24, 1997 - Thomas P. O'Brien P.S. recovered a 1" iron pipe with 4" aluminum cap as set by Frank J. Bray August 9, 1967. Witnesses found verify corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 1" iron pipe with 4" aluminum DNR cap stamped to identify.

Witnesses : (Fd.) 7" Cedar - S41°E - 21½ lks.
(Fd.) 9" Cedar - S43°W - 14 "
(Fd.) 12" Cedar - N79°E - 9.48'
NBT. 8" Cedar - N31°W - 34.50'
Carsonite Post - North - 1.0'



Signed by Thomas P. O'Brien P.S.

Date November 25, 1997

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 136