

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 14W	G2
	T R	
	T R	
2. Property Controlling in Section	S 3 T 46N R 14W	13
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4	3		2			1	
3													
4	7		8			9	10		11			12	
5													
6	18		17			16	15		14			13	
7													
8	19		20			21	22		23			24	
9													
10	30		29			28	27		26			25	
11													
12	31		32			33	34		35			36	
13													

I, Stephan J. Szyszkoski, in a field survey on G2 04/20/2010
13 04/28/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G2) Quarter corner common to Sections 3 and 4. 1850 - Established by Guy Carleton Deputy Surveyor.
Set post 40.12 ch. north of Section corner G3 and 39.72 ch. south of Section corner G1. Y.Pine 8"
S46E 46 links, Y.Pine 18" S71W 53 links. 1960 - Reestablished by Billy D. Buckler RLS "midway
between two Section Corners" [see below]. Set 1" pipe with 4" brass cap. 8" R.Pine N20E 19 links,
18" R.Pine N46W 86 links.

(13-Sec. 3) Southeast 1/16 corner, Section 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G2) The original post and accessories were not recovered. Found the 1960 monument in good condition
and at record bearing and distance from the 1960 witnesses, both in good condition. I note an error
in the 1960 record: The monument was found at the proportionate position between Section corners
(found 2646.82' south and 2618.30' north), not "midway and on line" as the record states. I accept
the monument as a careful and faithful reestablishment of the position of the original corner.

(13-Sec. 3) Established the corner at the intersection of straight lines connecting opposite 1/16
corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G2) Found 1"ID I.pipe with 4" brass cap.
Set measuring nail with MDNR tag in the side of:
18" R.Pine N27E 12.85' mrkd "1/4S" 1960 NBT
21" R.Pine N39W 57.7' do do
6" W.Pine N81E 8.4' mrkd "1/4S NBT"
8" J.Pine S82W 14.8' do
Bearings are magnetic.

(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" twin R.Pine S68W 53.7' mrkd "SE1/16 BT"
20" R.Pine N63E 36.85' do
7" R.Pine S19W 63.6' do
5" R.Pine S30E 87.9' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/01/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

