

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 20 T 46N R 15W	5
	S 20 T 46N R 15W	6
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 5 03/08/2011 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 20) North 1/16 corner, Section 20. Not established in the original survey.

(6-Sec. 20) Northeast 1/16 corner, Section 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 20) Established the corner midway and on a straight line between Quarter corner 1323.61' north and the intersection of 1/4 lines 1323.61' south.

(6-Sec. 20) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Cedar S82E 29.1' mrkd "N1/16 BT"
6" Cedar N57E 36.1' do
5" Balsam S72E 8.95' do
4" W.Birch S36W 13.7' do
Bearings are magnetic.

(6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
16" Cedar S68E 18.2' mrkd "NE1/16 BT"
14" Cedar S27E 20.4' do
9" W.Birch N84W 18.25' do
6" Cedar N15W 15.15' do
Bearings are magnetic.

Signed by

Stephan J. Szyszkoski


Date

05/05/2011

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities



47474

47475

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1971
Revised Jan., 1983
Revised Oct., 1995