

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| Schoolcraft (County) | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 46N R 15W | C9 |
| | T | |
| | T | |
| 2. Property Controlling in Section | S T | |
| | S | |
| | S | |
| 3. Miscellaneous Property in Sec. | S T | |
| | S | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 02/24/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C9) Corner common to Sections 19-20-29-30. 1961 - Reestablished by single proportionate measurement
to the original record N-S by Billy D. Buckler RLS. Set 1" Iron pipe with 4" brass cap. 5" Tamarack
S73W 107 links, 12" Norway Pine N81E 307 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) Found the 1961 monument in good condition and at record bearing and distance from the remaining
witness Norway Pine, now a burned stump. The Tamarack SW was not recovered. Accepted the monument
as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Pd. 1" ID I. pipe with 4" brass MI Dept. of
Conservation cap. Set measuring nail with
MDNR tag in the side of:
24" W. Pine S28W 158.39' mrkd "S30 NBT"
5" Tamarack S52W 71.86' do
10" Tamarack S89W 78.20' "S30 NBT"
10" W. Pine N42E 187.77' "S20 NBT"
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 05/05/2011
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities