

SURVEY &
REMONUMENTATION

MAR 05 1998

SECTION

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Kingston Township

Tuscola Located In: Corner Code #
(County)

1. Public Land Survey	T12N R11E	J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth D. Dunton, in a field survey on Oct. 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


March 18, 1834 Hervey Parke, D.S. Set quarter section post. Beech 10" N24°W 12 1/2 links, Birch 10" N64°E 28 links. Aug. 1, 1963 M.S.H.D. witness card by Donald C. Pyle, R.L.S. #3165. Found 1" pipe buried 2'. N50°E 55.38' 10" Elm, S30°E 38.48' 12" Elm, S45°W 43.60' 7" Maple, sketch on card shows 2644.62' to corner I-13, T12N-R11E, 101.57' to cor. J-1, T11N-R11E and 2603.81' to corner K-1, T11N-R11E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe in monument box. The 1963 accessories have been obliterated but the distances shown to the adjacent corners check relatively well. Accepted 1" pipe in monument box as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed standard brass cap over 1" pipe found in monument box. Stamped cap J-13, T12N-R11E. Encased cap in concrete in monument box.
North 1.15' E-W centerline conc. pavement M-46.
N70°E 39.20' left edge conc. pavement @ sta. 115+16 (pave. joint).
S75°E 36.65' right edge conc. pavement @ sta. 115+16 (pave. joint).
West 101.49' fnd. 1" pipe in monument box at apparent corner J-1, T11N-R11E.

Signed by 
Surveyor's Michigan License No. 23503

Date

11-10-97

APPROVED
11-10-97
J.M.F.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
REVISED OCT., 1995

