

APR 05 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:

CITY OF DETROIT

Corner Code #

1. Public Land Survey

T 1 S R 12 E

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

009

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 5 1995
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims POINT COMMON TO PC#100 & #679 @ CENTERLINE OF MACK AVE.

I, MARTIN C. DUNN, in a field survey on OCTOBER 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO CORNER SET IN ORIGINAL GOVERNMENT SURVEY.

PLATS

L. 8 P. 82

L. 10 P. 59

L. 11 P. 18

L. 22 P. 36

L. 24 P. 42

PLAT OF SUBDIVISION OF LOTS 38, 39, 40, & 40, VANDYKE FARM

THOMAS & CAMERAN'S SUBDIVISION OF LOTS NO. 28, 29, 30, 31, & 32, VANDYKE FARM

MISS L. THORBURN'S SUBDIVISION OF LOTS 42 & 43 OF VANDYKE FARM

PHILIPP KRAMER'S SUBDIVISION OF LOT NO. 41, VANDYKE FARM

HUGO SCHERER'S SUBDIVISION OF PART OF LOTS 33 & 34, VANDYKE FARM

APRIL 24, 1885

MAY 16, 1887

NOVEMBER 19, 1887

JULY 11, 1901

DECEMBER 13, 1905

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER

HELD FOUND CORNERS ALONG NORTH SIDE OF MACK. HELD LINE BETWEEN FOUND IRON WEST SIDE OF VANDYKE TO FOUND IRON NORTHWEST CORNER VANDYKE AND MACK. OFFSET LINE RECORD DISTANCES.

VERIFIED LOCATION WITH OTHER FOUND IRONS AND STONE CURB SPLITS.

PLACED WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" IRON WITHIN A MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

T.2S., R.12E.

WAYNE COUNTY REMONUMENTATION MARKER AND ALUMINUM CAP #30081 ON 1/2" x 18" ROD IN MONUMENT BOX.

WITNESSES

AZ 25° 41.37' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK

AZ 115° 42.21' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK

AZ 203° 42.47' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK

AZ 287° 46.29' SET PK NAIL WITH W.C.R. TAG IN CONC. WALK

THE SELECTED LOCATION IS FOR THIS PROPERTY CONTROLLING MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION INDICATED.

Signed by

Martin C. Dunn

Date


DECEMBER 5, 1995

Surveyor's Michigan License No.

30081

95263097

95 DEC -8 PM 2:12
FOREST E. YOUNGBLOOD
REGISTER OF DEEDS
CLERK OF COURT



4
7D
MR.