

SURVEY &  
REMONUMENTATION

MAY 10 2000

RECEIVED

1999 DEC -1 PM 3:05

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in SECTION

WEXFORD COUNTY

Located In:

Corner Code #

1. Public Land Survey T 21N R 09W I-2  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, George D. Smith, P.S., in a field survey on June, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-2) 1848 GLO Subdivision by Orson Lyon D.S. Hemlock 20-S75E-12, N. Pine 19-N64W-36.  
1881 A.J. Teed Liber 1, Page 01. Corner found no description. N. Pine 18-N31 3/4E-31 2/3, N. Pine 12-S13 1/2E-34.  
1891 A.J. Teed Liber 1, Page 02. Corner found no witnesses or description given.  
1906 D. Teed Liber 1, Page 03. Found government witness. W. Pine 30-S38W-34 3/4, N. Pine 24-N65E-12 1/3.  
1907 D. Teed Liber 1, Page 04. Corner found legend shows gas pipe.  
1966 Roser PS #12028 Government witness record Liber 02, Page 900. Found 3/4" pipe, corner fits Teed survey data, 22" maple-N50E-89.86, 26" oak-S60W-68.42, Powerpole-S20W-78.85, 3/8" iron-S45W-46.64.  
1977 Fletcher PS #19830 Certificate of Survey Liber 01, Page 507. Corner found no description given. Powerpole-S75W-29.70, Powerpole-N45E-40.30, 14" Aspen-S80E-22.80.  
1981 J. Wilcox PS 14102 Certificate of Survey, Liber 1, Page 886. Found 3/4" pipe, witnesses same as 1966 Roser.

A continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- I-2) Found 1/2" iron and three witnesses from 1966 Roser's PS #12028 government witness card, two witnesses from 1994 Geers PS #33977 Certificate of survey and one from 1998 Pullen PS #39095 Certificate of Survey. This corner is accepted as a careful and faithful perpetuation of the position of the original corner being the quarter corner common to Sections 2 and 3, T21N, R9W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-2) Replaced 1/2" iron with 5/8"x36" iron with brass cap stamped 2, 3 1999 PS #39098.  
S61W 68.00 36" oak (Roser)  
N57E 90.00 36" maple (Roser)  
N45W 27.90 Powerpole (1998 Pullen 27.94)  
S45W 30.72 12" oak (1994 Geers 30.67)  
S24W 79.10 Powerpole (1966 Roser 78.85)  
S33E 46.80 12" maple (1994 Geers 46.76)  
N55E 42.65 Tel. Pole (1998 Pullen 42.68)

Peer Group Reviewed and Approved

Date: 12 Nov 99  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor



LIBER 05 PAGE 177

Signed by George D. Smith  
Surveyor's Michigan License No. 39098

Date 11-12-99