

SURVEY &
REMONUMENTATION

COPY

MAY - 1 1995

RECORDED
WASHTENAW COUNTY, MI

JAN 10 9 41 AM '95

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Washtenaw
(County)

Located In:

Corner Code ##

- | | | | | | |
|---------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 2S | R | 7E | L-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |

PEGGY M. HAINES
COUNTY CLERK/REGISTER

- COPY -

LIBER

1 PAGE 238 RM

- COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kenneth R. Coleman, in a field survey on December 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No date S. Pettibone Compiled drawing
3) 30" W. Oak N37°E 89 lnks
4) 30" W. Oak S76°W 1.54 ch

1942 Atwell-Hicks, Inc. Survey by others
Corner used in survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" x 4' bent I.P. Spun, removed and reset with a 1" x2' I.P. w/remon. ca;

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x2' I.P. w/remon. cap
Twin 4" x 8" Ash S45°W 0.53 to nail w/W.C.R. tag
6" Elm N10°W 7.15 to nail w/W.C.R. tag
12" Elm N80°E 6.65 to nail w/W.C.R. tag
4" Cherry N 5°E 8.38 to nail w/W.C.R. tag

APPROVED

DATE 12/22/94

CO. REP. KA


I conclude that this corner is accepted as the best available evidence of the position of the original corner.

Signed by

Kenneth R. Coleman

Surveyor's Michigan License No.

37271



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983