

RE

FILED

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

00 FEB -1 AM 8:37

SECTION

For corners in
Allegan (County) Located In: Corner Code #

1. Public Land Survey T2N__ R15W__ B-11
T__ R__
T__ R__ North 1/4 corner
T__ R__ Section 31
Clyde Twp.,

2. Property Controlling S__ T__ R__
in Section S__ T__ R__
Property in Sec. S__ T__ R__

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Joyce A. ...
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

1000007 MAR 2005

I, Steve Lampen, in a field survey on December 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11 1975 - D. Bonnema - Recorded survey L875, P508
GLO - 1831 - C. Britain 1/4" iron
Set post N and B.C. in SE side 10" Pine NE 50.93'
Hemlock 8 S 59 E 9 N and B.C. in E'ly side 20" W. Cherry NNW 72.81'
Birch 9 N 59 W 31 SE corner of house foundation WNW 134.42'
N and B.C. in N'ly side 12" W. Cherry SW 56.31

1973 - G. Mitchell
30" Box Elder N 45° W 72.90' 1975 - D. Bonnema - L.C.R.C., L2, P396
8" Cherry E 56.45' 1/4" iron
10" Cherry S 50 W 56.34' Same witnesses as L875, P508

1986 - R. Moored
1/4" iron
Same witnesses as L875, P508 and L2, P396

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-11 Found 1/2" iron 8" Cherry E 56.45' 10" Cherry S 50 W 56.34' N and B.C. in SE side 10" Pine NE 50.93' SE corner of house foundation WNW 134.42' N and B.C. in N'ly side 12" W. Cherry SW 56.31'


Pulled 1/2" iron and set Standard Allegan County 3/4"x24" remonumentation iron with red cap #23520.

Approved by the Allegan County remonumentation Peer Group on December 28, 1999 and is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 28, 1999
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-11 Standard Allegan County 3/4"x24" remonumentation iron with red cap #23520
Azimuth = Michigan State Plane grid direction

14" Pine with remonumentation tag NW side	49° 45'	50.85'
12" Cherry with remonumentation tag S side	92° 31'	56.55'
10" Maple with remonumentation tag N side	269° 04'	37.86'
NE corner house siding	309° 42'	151.36'



Signed by Steven Lampen

Date DECEMBER 31, 1999

Surveyor's Michigan License No. 37279