

LAND CORNER RECORDATION CERTIFICATE
Feeling Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 13 T 47N R 34W	3
	S 13 T 47N R 34W	4
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on 3 08/27/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 13) North 1/16 corner between Sections 13 and 14. 1980 - Established by K.L.Sackett RLS midway and on line between corners north and south. Set 1"IDx32" I.pipe with 4" alum. cap. 6" Balsam S07E 33.1', 4" Balsam S07W 35.9', ROW marker N19E 27.8'.

(4-Sec. 13) Northwest 1/16 corner, Section 13. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 13) Found the 1980 monument in good condition and at record bearing and distance from the 1980 witnesses. The Balsam BT SE is a stump. The Balsam BT SW is a dead stub. The ROW marker is in place and in good condition. Accepted the monument as a careful and faithful establishment of the position of the corner.

(4-Sec. 13) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Balsam S11W 23.45' mrkd "1/16S BT"
 4" Tamarack S13W 18.75' do
 3" Poplar S54W 37.65' do
 Top center of conc. R/W marker N22E 27.8'
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set measuring nail with MDNR tag in the side of:
 23" W.Pine N45E 22.0' mrkd "1/16S BT"
 14" W.Pine S22E 23.5' do
 5" Spruce S60W 7.15' do
 10" Maple N36W 20.25' do
 Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/22/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities