

RAIIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

**BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 SEP 20 AM 9:47

BERNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

For corners in

Barrien (County) Located In: Corner Code #

1. Public Land Survey T 4S R 17W I-10
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on 9 April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 WILLIAM BROOKFIELD, D.S.
SET 1/2 MILE POST
16" W. OAK S 56° W 7 LINKS
13" W OAK N 60° E 18 LINKS
- 1907 WILL J. CLEARLY, COUNTY SURVEYOR
STONE NO WITNESSES
- 1952 MICHIGAN DEPARTMENT OF TRANSPORTATION
CORNER IS 11.15' WEST OF CENTERLINE OF M-140
- 1974 WIGHTMAN & ASSOCIATES, INC.
(IRON PIPE)
POWER POLE S 45° W 56.23'
CONC. R.O.W. MARKER S 25° W 92.55'
CENTERLINE OF M-140 EAST 11.30'
- 1977 WIGHTMAN & ASSOCIATES, INC.
(1/4" IRON PIPE)
CENTERLINE EAST 11.15'
PK NAIL IN PP S 60° W 56.29'
PK NAIL IN GUARD POST N 25° W 51.85'

09/20/99 111#2952 A55
CORNER \$7.00
09/20/99 111#2952 A55
STATE REMON FEE \$2.00

SURVEY &
RF
DEC 28 1999
SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REBAR @ WEST EDGE OF PAVEMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED 1/2" REBAR, RESET WITH 1" X 3' IRON PIPE WITH B.C.R.P. BRASS CAP IN MONUMENT BOX

WIT TAG IN PP S 60° W 56.25'
WIT TAG IN PP N 10° W 118.48'
WIT TAG IN PP N 80° E 75.91'
CENTERLINE OF CONCRETE PAVEMENT EAST 11.28'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 26469

Date 17 SEPT 1999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995