

SURVEY & REMONUMENTATION

MAR 03 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in: Ada Township	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>10W</u>	<u>I-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

Eric J. Kohn

97 OCT 15 AM 8:51

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

10221

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehhouse, in a field survey on January 31 19 97, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10	1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1961	Witness Map	K.C. Surveyor	Iron	PEER APPROVED <u>5/22/97</u>
	1973	L.C.R.C. #533	Exxel Engineering	1/2" Iron	CHAIRMAN <u>Randy Kolehhouse</u>
	1973	L.C.R.C. #672	Medema, Van Kooten & Assoc.	3/4" Iron	
	1981	L.C.R.C. #2591	Jonker Land Surveys	Fnd. 1/2" Round Iron / Set K.C. Monument	
	1994	L.C.R.C. #8075	Glaza & Associates	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Jonker Land Surveys on 12/22/81 and was recorded per L.C.R.C. #2591.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found a Standard Kent County Monument 300' M/L East of the C/L of Honey Creek Avenue (bit.) running Northerly and Southerly on line of a tree row and fence line running East per L.C.R.C.'s #2591 and #8075 as set by Rob Jonker in place of a 1/2" round iron he found which checked L.C.R.C.'s #672, #533 and the K.C. Surveyor's records.

L.C.R.C. #2591

Remon. tag on E side 16" Oak S 42° W 5.33'
 Remon. tag on E side 14" Oak S 01° W 12.15'
 Remon. tag on N side 12" Oak S 89° W 17.28'
 Remon. tag on N side 24" Oak S 82° E 56.54'

L.C.R.C. #8075


K.C. remon tag & nail in E side 16" Oak S 42° W 5.23'
 K.C. remon tag & nail in E side 14" Oak S 01° W 12.18'
 K.C. remon tag & nail in N side 14" Oak S 89° W 17.26'
 K.C. remon tag & nail in N side 24" Oak S 82° E 56.45'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard Kent County Monument

Nail & K.C. remon. tag on E side 16" Oak S 42° W 5.23'
 Nail & K.C. remon. tag on E side 14" Oak S 01° W 12.18'
 Nail & K.C. remon. tag on N side 14" Oak S 89° W 17.26'
 Nail & K.C. remon. tag on N side 24" Oak S 82° E 56.45'



Signed by *Randy J. Kolehhouse* Date 8-1-97

EARTH TECH

Surveyor's Michigan License No. 25854