

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 94 DEC -6 AM 9:01

Filing Requirement of Act 74, Mich. P.A. 1970

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

Tracy J. Kulehouse
REG. OF DEEDS

7786

Register of Deeds Stamp & File Number

For corners in

Kent
(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>7N</u> | R <u>11W</u> | <u>D-1</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kulehouse, in a field survey on July 5 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- D-1 This corner was not originally set by the G.L.O.
- | | | | |
|------|----------------|-------------------|--------------------------------|
| 1937 | Wit. Map | K.C. Surveyor | Iron |
| 1978 | L.C.R.C. #1144 | Exxel Engineering | P.K. Nail |
| 1981 | L.C.R.C. #1415 | Williams & Works | Capped Iron |
| 1982 | L.C.R.C. #3170 | Jonker | Fnd. Capped Iron/Set K.C. Mon. |
| 1990 | L.C.R.C. #5742 | Bueche | K.C. Mon. |

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/3/94
CHAIRMAN Randy Kulehouse

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Robert Joner on 11/10/82 and was recorded per L.C.R.C. #3170.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-1 Found standard Kent County Monument in the left turn lane of 4 Mile Road (E-W) 30' M/L West of C/L of Fuller Avenue North per L.C.R.C.'s #3170 and #5742 as set by Rob Jonker in place of an Exxel Engineering capped Iron he found which checked L.C.R.C.'s #1144 and #1415. This corner is common with D-13 T8N R11W.

L.C.R.C. #3170

L.C.R.C. #5742


SE cor. hse. fnd. (0.5' up) N 10° W 53.40'
C/L pavt. to N East 30'

SE cor. hse. fnd. (0.5' up) N 10° W 53.34'
P.K. in W side C.P. pole S 10° E 25.16'
Nail & remon. tag in E side 10° Oak S 40° E 69.65'
C/L blacktop N East 30' ±

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 Standard Kent County Monument
SE cor. hse. fnd. (0.5' up) N 10° W 53.34'
P.K. in W side C.P. pole S 10° E 25.16'
Nail & K.C. remon. tag in E side 10° Oak S 40° E 69.65'
C/L blacktop N East 30' ±



Signed by Randy J. Kulehouse
Surveyor's Michigan License No. 25854

Date 12/1/94