

**SURVEY &
REMONUMENTATION**

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 21

FILED

10:52 A.M.

OCT 28 1994

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-----------|-----------|-----|
| 1. Public Land Survey | T - 6 - S | R - 3 - E | J-3 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 10 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January 1824, John Mack set 1/4 post W. Oak 20 N 40 W 19, W. Oak 30 S 29 E 21
May 1838, Survey of Sec. 11 shown in Satterthwaite book but monuments are not described.
July 1948, During a survey for road re-construction a stone was found.
November 1971, K.L. Suydam found a 1/2" iron pipe, nail & washer in 18" Ash NW 59.60.
November 1972, K.L. Suydam recorded it in L. 1, P. 231, nail & washer in 18" Ash NW 59.60.
December 1972, W.E. Sommer recorded it in L. 1, P. 111, nail & washer in 18" Ash NW 59.60.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 10, 1994, Found iron pipe in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
SW cor of garage (wood foundation) N 35° W 141.75
Fd. dbl. hd. nail & disc in 24" Ash N 20° W 59.58
Fd. dbl. hd. nail & disc in 28" Ash S 80° E 148.36
Fd. dbl. hd. nail & disc in Elec. Pole S 10° E 79.66
Fd. dbl. hd. nail & disc in 10" Ash N 70° W 93.15



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994

Signed by Glenn E. Richard Date Oct 19, 1994

Glenn E. Richard

Surveyor's Michigan License No. 13040