

SURVEY & REMONUMENTATION

FEB 25 1999

SECTION

FILED

1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 OCT 14 P 2:11

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

For corners in

Livingston Located In: Corner Code #
(County)

- 1. Public Land Survey T 4N R 4E L-7
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number
LSC 911M

I, John H. Rauser, P.S., in a field survey on September 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

Table with 13 rows and 13 columns (A-M) containing numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 Common 1/4 Corner, Sections 13 & 24, T4N-R4E, Cohoctah Township, Livingston County
1823 Wood post placed by John Mullett, D.S.: B. Oak 24" N25E 1.83 lks
W. Oak 24" N78.5W 1.5 lks


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Common 1/4 Corner, Sections 13 & 24, T4N-R4E, Cohoctah Township, Livingston County
Found a concrete monument with aluminum cap stamped "D.L.B. #18655 MDNR" as recorded by Donald L. Bissell in 1981.
No evidence of the original government corner or the county survey was recovered by Bissell in 1981.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Common 1/4 Corner, Sections 13 & 24, T4N-R4E, Cohoctah Township, Livingston County
Left found concrete monument with brass cap, stamped "D.L.B. #18655 MDNR", in place as recovered
N05E 39.10' Set remon tag above fnd nail in SE fc 12" Oak
N72E 34.20' Set remon tag above fnd nail in N fc 12" Ash
South 26.79' Set remon tag above fnd nail in W fc 12" Ash
N45W 28.84' Set remon tag above fnd nail in NE fc 10" Oak.

Signed by John H. Rauser
Surveyor's Michigan License No. 39096



Date 9/30/98
APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1974
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 6-3-98 CO. REP JED