

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Machine Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S. R. <u>8</u> E. W.	<u>C-9</u> <u>B-9</u> <u>D-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11/21 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- C-9 Sec. Cor. 19-20-29-30, set during original survey, about 1840.
- B-9  $\frac{1}{4}$  Corner bet. Secs. 19-30, original witnesses were small Tamarack.
- D-9  $\frac{1}{4}$  Corner bet. Secs. 20-29.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- C-9 Corner re-established by proportionate distance, bet. Cors., one mile to East and to West. Placed the corners on this two miles, on a straight line, since we had nothing definite to North and South. The Pine ridges were not noted, in the original calls.
- B-9 Explanation above.
- D-9 Explanation above.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Placed 1" pipe with 4" aluminium cap at all three corners.

- C-9 New Bearings: 10" W. Pine S49°E 45.6' and 9" W. Pine S54°W 62.4'  
 Corner lies 50' North of a Pine Ridge.
- B-9 New Bearings: 9" Cedar S71°W 14.5' and 12" Cedar N8°E 45.2'  
 Corner lies in thick swamp.
- D-9 New Bearings: 9" Cedar N62°E 20.0' and 6" Cedar N20°E 14.4'

SIGNED BY Billy D. Buckler DATE 12/20/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 88.7 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_