

FEB 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

| For corners in Osceola | Located in: | Corner Code# |
|---------------------------------------|-------------|--------------|
| 1. Public Land Survey | T 18 N | R 8 W |
| | T | R |
| | T | R |
| | T | R |
| 2. Property Controlling in Section | T | R |
| | T | R |
| 3. Miscellaneous Property in Sec. | T | R |
| | T | R |
| 4. Lot No. _____ Recorded Plat | | |
| 5. Private Claims | | |

OSCEOLA COUNTY
 REGISTER OF DEEDS
 99 NOV 19 PM 12:09
Mary Campbell

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on October 5, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

G-6 - 1/4 Corner common to Sections 15 & 16, T18N, R8W, Osceola Co., Mi.

A. Description of original monument and accessories and/or subsequent restoration:

1848 - O. Lyon, G.L.O.
 #1 - 12" Beech N36°E 30 Links
 #2 - 11" Beech S42°W 23 Links

1891- 1904 - Temple/ Trumbull
 Osceola Twp., had a remonumentation program. Set 3" Clay Tiles.

Osceola Twp. Book (Undated)
 Page 5 (Front)
 Rod
 #3 - 16" Maple N.E. 30.3'
 #4 - Maple S.W. 36.9'

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1" x 24" pipe at surface of road. Directly below the pipe at a depth of 30" I found a 1/2" rod inside a 3" Clay Tile. Corner is in line with fences East and West and in the center of North and South road.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found dead.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1" Pipe with a 1" x 18" Pipe with Osceola County Remon Cap, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 8" Ash S47°E 35.87' (60d spike in N.E. side)
- 6" Ash S45°W 48.11' (60d spike in S.E. side)
- 7" Ash N86°W 28.09' (60d spike in S. side)
- 20" Maple N64°E 51.92' (60d spike in N.W. side)



APPROVED LAND CORNER
 P.A. 345 OF 1990
 Osceola County

10-21-99

R. L. W.

Signed by Robert L. Wetherell

Date Nov. 9, 1999

Surveyor's Michigan License No. 24624