

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHN
 Ontonagon County
 LC 3/348 JEM Fee: 9.00
 10/19/95
 14:33
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>39W</u>	G-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



I, Joseph C. Domitrovich, in a field survey on October 2, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:
1/4 Corner Sections 21 and 22, T52N, R39W

1845 - Willam A. Burt set 1/4 section post
 16" Yellow Birch N 37° E 24 links
 8" Sugar N 63° W 34 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found no evidence of original corner.

Found a 1" diameter mushroomed pipe at the corner of an old fence running north and west. The pipe appears to have been set by single proportionate measurement.

Accepted corner position and replaced with a county monument.


(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner is an aluminum pipe with 3" diameter aluminum cap at the corner of fences north and west.

Witnesses:

10" Hard Maple	N 15° E	34.36'
10" Yellow Birch	N 76° E	25.03'
8" Hard Maple	S 23° W	21.27'
12" Corner Fencepost	N 25° W	1.26'
Sign Post	South	1.11'

PEER GROUP APPROVED
Earl W. Applbaum 10-18-95
 COUNTY REPRESENTATIVE



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich Date 10/18/95
 Surveyor's Michigan License No. 37273