

MAY 16 1997

COMMISSION

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

DATE 12/10/96

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T42NR15W	J-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Received & Filed this 30 day of Dec. 1996 at 9:27 A M Sigrid I. Hedberg Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Thomas P. O'Brien in a field survey on Dec. 12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9													X	
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration: J-9 Sept. 13, 1850 - Algernon Merryweather D.S. set qr. section post. Balsam 12 in. N43E 25 links d0. 12 in. S35W 22 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: J-9 Dec. 12, 1996 - Thomas P. O'Brien, P.S. re-established corner by single proportionate measurement in fence line to West. Corner falls in ceterline of county road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: J-9 Schoolcraft County monument stamped to identify.

- Witnesses:
- 6" Cedar - N25°E - 59.40'
  - 24" Maple - S4½°E - 211.63'
  - 8" Red Pine - S81°W - 107.67'
  - 18" Maple - N18°W - 76.84'



Signed by Thomas P. O'Brien Surveyor's Michigan License No. 21274

Date Dec 26, 1996