

MAR 04 1998

# LAND CORNER RECORDATION CERTIFICATE

SECTION **FILING REQUIREMENT OF ACT 74, MICH. PA 1970 LAND CORNER**  
1997 Alcona County Remonumentation **PA 345 of 1990**  
**ALCONA COUNTY**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 25N S., R. 5E E. W.	W-1/4 cor. 20 C-8
2. PROPERTY CONTROLL- ING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Date 7/14/97  
County Rep. D. A. Gauthier  
**RECORDED**  
Date September 8, 1997  
REMON LIBER 1 PAGE 256  
2:20 Time P M  
Doris A. Gauthier  
**Doris A. Gauthier**  
**REGISTER OF DEEDS**  
  
REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on Aug. 20, 1997, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

1845: G.L.O. - set post and referenced  
1900: W. Chapelle - set post and referenced  
1933: Dependent resurvey - set 6" x 24" conc. mon. w brass tablet  
1973: R. Miller - no desc. of cor.  
1977: R. Miller - placed 1/2" rod and cap  
1991: Rowe Eng. - fd. 1/2" bar - placed 6"x 6" x 36" conc. mon.


**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

fd. pavement box with U.S.F.S. mon. with four (4) accessories from Rowe Eng. survey and corner recordation (1991) as shown in Liber 252, P. 389 and L. 2 C.R.C., P. 14.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Pavement box with conc. U.S.F.S. monument

references: Carsonite post / East / 33.00 ft  
10" r. pine / N 28°W / 111.96 ft  
10" r. pine / S 85°W / 86.50 ft  
10" r. pine / S 32°W / 127.85 ft



SIGNED BY \_\_\_\_\_ DATE 9-8-97

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_