

SURVEY & REMONUMENTATION

FEB 07 2001

2000 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alcona (County)	Located in:	Corner Code #
1. Public Land Survey	T26N R7E	C-2 ✓
	T R	Millen Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Alcona County
Remonumentation

Liber 2 Page 73

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:42 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Thomas L. Fabis, in a field survey on Sept. 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838: G.L.O. Survey Lewis Clason set post & referenced: Beech 12 S80E 10, do 12 S81W 45
1965: Co. Hwy. Plans 3/4" Pipe & referenced.
1990: R.S.Scott Survey Liber 224 Pages 119 thru 121 David Guthrie ex. 1/2" Iron Rod and referenced.
1993: Revised R.S.Scott Survey Liber 271 Pages 102 thru 104 David Guthrie ex. 1/2" Iron Rod and referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2000: Found 1/2" iron rod capped N.E.L.S. 7' West of centerline of (Bit. surface) Stout Road. Also found 20" Birch Stump N35E 102.2. This 1/2" iron rod is in S.P. position. No other existing witnesses. The position of this corner harmonizes with the 1990 survey by David Guthrie.

The position of this corner is compatible with local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2000: Removed existing plastic cap and replaced with a 3" dia. brass cap, stamped to identify the corner, over the existing 1/2" iron rod. Installed a Mon. Box over the corner. Reestablished Witnesses are:
Centerline of steel gate post N50E 55.07
Set tag #31591 in P. Pole S72E 38.10
Set tag #31591 in 4" Ash N72W 47.60
Set tag #31591 in 13" Maple N54W 79.15

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date: 8-28-2000
County Rep. P.D.P. Galt

Signed by Thomas L. Fabis
Surveyor's Michigan License No. 31591



Date September 12, 2000