

SURVEY &
REMONUMENTATION

RECORDED

1994 ~~APR 25 1995~~ Alcona County Remonumentation Corner

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Alcona
(County)

Located In:

Corner Code #

1. Public Land Survey T 26N R 7E G-5
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 7 2 09 PM '94

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Alcona County
Remonumentation
Liber 1 Page 71
E.T.L.

Register of Deeds Stamp & File Number

David B. Guthrie in a field survey on June 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


- 1846: G.L.O. Survey by J.W. Mullett - Set post and referenced
Hem 20 - N67W - 38 / Beech 10 - S84E - 37
1903: Survey by Edw. Chapelle - Post
1917: Survey by edw. Chapelle - Post
1955: M.D.S.H. Survey - 3/4" Iron Pipe
1986: Survey by D.R. MacNeill and Associates - Found Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1994: Found 1" Iron Rod in Monument Box 9 feet South of the intersection of Hwy. M-72 and Sanborn Road North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1994: Replaced with 5/8" Iron Rod with a 3" Brass Cap stamped to identify the corner placed in a Monument Box.
Referenced -
S38°W - Anchor Pole - 79.63 feet
S05°E - 12" Beech - 78.12 feet
S28°E - 20" Beech - 92.56 feet
N10°E - Utility Pole - 116.75 feet



Signed by

David B. Guthrie

Date

Nov. 5, 1994

Surveyor's Michigan License No.

22435