

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 17W H9

2. Property Controlling  
in Section

S T R

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/02/2012 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H9) Quarter corner common to Sections 22 and 27. 1958 - Reestablished by Billy D. Buckler RLS midway and on line between two Section corners. Set 1" pipe with 4" brass cap. 9" H.Maple N32W 28 links, 14" H.Maple S67W 35 links. 1981 - Note in MDNR Newberry Office file by W.Miller: 14" H.Maple S67W 35 lks was cut during logging operation. Only stump base remains. Also no monument found. Set 5" cedar scribed post at corner location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H9) The 1958 monument was not found. Found a squared cedar post at record bearing and distance from the 1958 witnesses. Remonumented the position for the corner at record bearing and distance from the 1958 witnesses: The H.Maple NBT NW is now 13" DBH and in good condition with old blazes visible. The H.Maple NBT SW is a burned stump. The remonumented 1958 position was found to be 1.19' south and 1.40' east of the record position midway between Section corners and I accept same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
13" Sugar N33W 19.15' mrkd "1/4S" 1958 NBT  
7" Sugar N81E 38.55' mrkd "1/4S NBT"  
13" Maple S15W 41.0' do  
9" Maple S52W 29.4' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/26/2012

For the Michigan Department of Natural Resources, Forest Resources Division