

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| Alger | Located In: | Corner Code # |
|----------------------------|-------------|---------------|
| (County) | | |
| 1. Public Land Survey | T 47N R 17W | C4 |
| | T 47N R 17W | D3 |
| | T R | |
| | S T R | |
| 2. Property Controlling | S T R | |
| in Section | S T R | |
| 3. Miscellaneous | S T R | |
| Property in Sec. | S T R | |
| 4. Lot No. , Recorded Plat | | |
| 5. Private Claims | | |

May 19 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C4) Quarter corner common to Sections 7-8. Reestablished in 1958 by Billy D. Buckler midway and on line between Section corners. Set 1" pipe with 4" brass cap. 6" H. Maple N20E 65 links, 12" H. Maple N55W 69 links.
(D3) Quarter corner common to Sections 5-8. Remonumented in the original position by Billy D. Buckler, RLS in 1956. Set 1" I. pipe with 4" brass cap. 16" Y. Birch S21E 28 links, 12" Cedar N87W 29 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C4) Found and accepted a 1.5" iron pipe with fitting attached on top and at record bearing and distance from the 1958 witness trees, both in good condition with overgrown blazes. The 1958 monument was not recovered. The corner is N58W 10.3' from the 1958 midway position as I have determined it this date (5.4' north and 8.8' west). This position has been used by others to subdivide Sec. 8.
(D3) Recovered the 1956 monument in good condition and at record bearing and distance from the 1956 witnesses, now both standing dead. Found no evidence of the original 8" Cedar noted in the 1956 record. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---|
| (C4) Found 1.5" dia. I pipe with fitting. Blazed, scribed, and set measuring nails in: | (D3) Found 1" I.O. pipe with 4" brass cap. Blazed, scribed, and set measuring nails in: |
| 6" twin Maple S39E 31.75' "1/4S NBT" | 9" Cedar S30W 4.85' "1/4S NBT" |
| 5" Maple N82W 4.9' do | 7" Cedar S47W 23.35' do |
| The 1958 NBTs: | 5" W. Birch S53E 30.85' do |
| 8" Maple N22E 43.2' "1/4S" | 5" Balsam N25E 7.3' do |
| 14" Maple N51W 46.1' do | Bearings are magnetic. Distances are to nail with tag. |
| Bearings are magnetic. Distances are to nail with tag. | |



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 8/5/04

For the Michigan Department of Natural Resources, Office of Land and Facilities