

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
(County)

Located In:

Corner Code F1

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-----------|
| 1. Public Land Survey | T | <u>1N</u> | R | <u>15W</u> | <u>F1</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Gary C. Bilow, in a field survey on January 19, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F1: Post not established by U.S. Government survey. Records obtained from Wightman-Moored dated 1969 of a survey performed by D. Ratekin (PS #8781) show this corner being reestablished by projecting the West line of Fairmont Park Plat North to the Section line to establish the 1/16th corner (code #2) and then doubling the distance from the Northeast corner of Section 4 through the 1/16th corner to reestablish the North 1/4 corner of Section 4 setting a 1" Iron - accessories: 8" twin Cherry WSW 29', 3" Oak W 5.5', 6" twin Oak S 6.0', 8" twin Oak NE 11.8', Centerline trail SW 64', South 1/4 corner Section 33 T2N R15W W 122.67'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F1: Found 3/4" Iron bar 122.71' East of the South 1/4 corner of Section 33 T2N R15W but none of Ratekin's witnesses. Accepted this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F1: Found 3/4" Iron bar
 S35E 62.44', Nail & Tag in 14" Pine
 N73E 74.56', Nail & Tag in twin 13" Pine
 N32E 68.53', Nail & Tag in twin 9" Pine
 West 122.71', 3" x 6" plate on top of
 Iron pipe (S 1/4 cor Sec-33 T2n R15W)



Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date

3/5/93