

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W T T	C12
2. Property Controlling in Section	S 5 T 47N R 34W S S	12
3. Miscellaneous Property in Sec.	S S S	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3				●									
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			●		32		33		34		35	
13													

I, Stephan J. Szyszkoski, in a field survey on C12 Aug 7 2012
12 Aug 8 2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C12) Quarter corner common to Sections 31 and 32. 1852 - Established by Z.B.Searles Deputy
Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set
post. Spruce 8 S31W 16 links, Spruce 4 N71E 23 links.

(12-Sec. 5) South 1/16 corner of Section 5. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C12) Recovered the point of the original post at record bearing and distance from the rotting
remains of the Spruce BT found S39W (mag.) 11.5' distant, no markings visible. The post is now
3"x3"x6" long, squared above the tapered point, found approx. 1 ft. below the moss surface in ground
water. The BT spruce NE was not recovered. To the south of and adjacent to the original post, I
found remains of 2 other posts, both smaller and both rotted, apparently set subsequent to the
original survey. Several overgrown blazes on adjacent trees face this position. Replaced the point
of the original post with a monument as described below.

(12-Sec. 5) Established the position for the corner midway and on a straight line between Quarter
corner 1311.06' south and the Center of Section 5 1311.06' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" Cedar N19°E 8.5' mrkd "1/4S NBT"
9" Tamarack S50°E 8.35' do
8" Tamarack S29°W 9.5' do
8" Cedar N05°W 9.2' do
Set sq'd cedar post adjacent.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" W.Spruce N28°E 22.5' mrkd "1/16S BT"
6" Sugar in clump N66°E 10.5' do
6" Sugar S27°E 30.4' do
9" Sugar West 13.4' do
Set sq'd cedar post adjacent.

Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/02/2013

For the Michigan Department of Natural Resources, Forest Resources Division

