

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 4 T 47N R 34W	15
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 10/28/2008 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(15-Sec. 4) West 1/16 corner between Sections 4 and 9. 1974 - Established by A.O.Enger RLS midway
and on line between Section corner 20.285 ch. West and Quarter corner 20.285 ch. East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 4) Recovered the 1974 monument in good condition and at record bearing and distance from the
accessories of record. Found the monument to be S44E 12.1' from the proper corner position and did
not accept the monument as marking the position for the corner. Established the corner midway and on
the Section line between Quarter corner 1329.65' east and Section corner 1329.65' west. The 1974
survey appears to suffer from at least two measurement errors made in the traverse between Section
corners E3 and G3. Removed the 1974 monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" Maple North 78.0' mrkd "1/16S BT"
6" W.Pine S77E 50.7' do
10" Maple S49E 45.9' do
9" twin Maple S37E 88.5' do
Set sq'd cedar post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/08/2009
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971