

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S 6 T 48N R 32W S _____ T _____ R _____ S 8 T 48N R 32W	2 (GCDB 160700) 1 (GCDB 220600)
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat	_____	_____
5. Private Claims	_____	_____

I, Stephan J. Szyszkoski, in a field survey on 10/27/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 6) East 1/16 corner between Section 6 T48N-R32W and Section 31 T49N-R32W. 1977 - K.L.Sackett RLS set a 1"IDx36" iron pipe with 4" aluminum cap on line between Section corner to the east and Quarter corner to the west. Witnessed by: 10" W.Pine N69°E 14.8'; 8" Cedar N78°W 40.8'; 7" W.Pine S66°W 28.4'; 10" squared Spruce N44°W 6.5'.

(1-Sec. 8) West 1/16 corner between Sections 5 and 8. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 6) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses. Determined that the 1977 position had been erroneously monumented 7.09' west of a position that is midway between corners B1 and C1. I did not accept the 1977 monument and subsequently removed it. Established the position for the corner midway and on the Township Line between Section corner 1317.03' east and Quarter corner 1317.03' west.

(1-Sec. 8) Established the position for the corner midway and on the Section line between Section corner 1316.55' west and Quarter corner 1316.55' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
15" W.Pine N52°E 8.9' old blazes (1977 witness)
10" Cedar N76°W 47.9' do do
4" Balsam S15°W 16.5' mrkd "1/16S BT"
4" Balsam N23°W 11.0' do
Set sq'd cedar post adjacent.
E= 7896475.825 N= 201997.820

(1) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
6" Balsam N15°E 3.15' mrkd "1/16S BT"
8" Maple N70°E 7.1' do
4" Maple S04°E 14.5' do
4" Balsam S76°W 12.2' do
Squared a 2" Balsam SE 1.2' no nail
E= 7897250.254 N= 200400.479

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum
Coord. Ref.=NGS PID RL1468: N= 199449.725 m. E= 7900599.998 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 03/18/2016

For the Michigan Department of Natural Resources, Forest Resources Division

