

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 33W	G7
	T R	
	T R	
2. Property Controlling in Section	S 16 T 48N R 33W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 10/04/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. 1981 - K.L.Sackett RLS found and accepted a 1/2" I.D.  
iron pipe. 11" Sugar N61E 15.0', 9" Sugar S19W 13.0', 9" Sugar N61W 37.0'.

(3-Sec. 16) North 1/16 corner between Sections 16 and 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) Found the 1/2" pipe of record, top bent over but sub-surface portion still set vertically, at  
record bearing and distance from the 1981 witnesses, now all rotted stumps. Accepted the monument as  
the best available evidence of the position of the corner and replaced it with a new monument.

(3-Sec. 16) Established the corner midway and on the Section line between Section corner 1323.31'  
north and Quarter corner 1323.31' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
4" Oak N45E 4.9' mrkd "S15 NBT"  
5" Ironwood N76E 14.85' do  
5" Balsam S07W 11.1' "S21 NBT"  
5" Balsam S79W 16.9' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
2" Blk.Spruce S23E 14.4' mrkd "1/16S BT"  
5" Tamarack S04E 84.15' do  
3" twin Tamarack S14W 55.7' do  
3" Tamarack S40W 77.9' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 01/12/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

