

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 33W	G8
	T 48N R 33W	I4
	T	
2. Property Controlling in Section	S T	R
	S T	R
	S T	R
3. Miscellaneous Property in Sec.	S T	R
	S T	R
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G8 06/20/2011 I4 08/03/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G8) Quarter corner common to Sections 21 and 22. 1852 - Established by Francis Houck Deputy Surveyor midway and on the Section line between Section corners 40.09 chains north and south. Set post. Sugar 16" N27W 11 links, Y.Birch 18" S66E 4 links. Found no subsequent record.

(I4) Quarter corner common to Sections 10 and 11. 1852 - Established by Francis Houck Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Spruce 14" S46E 25 links, Fir 18" N23W 9 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G8) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner position midway and on the Section line between monumented Section corners of record 2646.54' north and south.

(I4) The original post and accessories were not recovered. Found a 1.25" ID Iron pipe set firm, projecting 29" above ground, true bearing S 00 deg. 07'45"W 2637.50' from Section corner I3 (GLO = 2640) and true bearing N 00 deg. 03' 49"E 13197.32' from Section corner I9 (GLO = 13193.4'). I accepted the pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
5" Maple N07W 16.4' mrkd "1/4S NBT"  
7" Balsam S64E 10.65' do  
5" Balsam S57W 15.3' do  
5" Maple N50W 9.2' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

(I4) Found 1.25" ID iron pipe, firmly set. Set measuring nail with MDNR tag in the side of:  
5" Maple S79W 25.3' mrkd "1/4S NBT"  
8" Spruce N58W 15.55' do  
6" Maple N23W 26.35' do  
6" Cherry S11E 24.25' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 08/15/2011

For the Michigan Department of Natural Resources, Forest Management Division

