

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S 12 T 48N R 33W S 12 T 48N R 33W S _____ T _____ R _____	1 4 _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 06/12/2012
4 06/13/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 12) West 1/16 corner between Sections 1 and 12. Corner previously monumented but found no
record at courthouse.

(4-Sec. 12) Northwest 1/16 corner, Section 12. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 12) Found two existing bearing trees, marked with blazes and scribing. The monument was not
recovered, it likely having been removed by ditch maintenance in the past. Found no record of who
established the corner but it may have been the Michigan D.N.R. Reestablished the position for the
corner midway and on the Section line between Section corner 1321.18' west and Quarter corner
1321.18' east. The position for the corner falls in the bottom of the southerly ditch along US-41.

(4-Sec. 12) Established the position for the corner at the intersection of straight lines connecting
opposite 1/16 corners. From the position thus established, I found a 1"ID iron pipe N87E 8.6'
distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
14" Maple S32E 29.3' old scribing plain
9" twin Maple S70W 34.8' do
10" Maple S03W 11.1' mrkd "1/16S BT"
N'yly post of "Passing Lane Ahead" sign
N72W 72.85'
Bearings are magnetic.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Y.Birch N02W 18.85' mrkd "1/16S BT"
9" Y.Birch N78E 18.95' do
6" Cedar S57E 25.55' do
9" Maple S05W 5.65' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/04/2012

For the Michigan Department of Natural Resources, Forest Resources Division

