

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 31 T 49N R 32W	14
	S T R	(GCDB 200120)
	S 31 T 49N R 32W	10
3. Miscellaneous Property in Sec.	S T R	(GCDB 100120)
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 14 10/21/15
10 11/09/15 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 31) South 1/16 corner between Sections 31 and 32. 1988 - Established by K.L.Sackett RLS
midway and on line between C12 and C13. Set 1"IDx36" I.pipe with 4" alum. Cap. 9" Balsam N27°E
18.0'; 12" Spruce S42°E 30.5'; 10" Spruce S80°W 11.4'.

(10-Sec. 31) South 1/16 corner between Section 31 T49N-R32W and Section 36 T49N-R33W.
Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 31) Found the 1988 monument in good condition and at record bearing and distance from the
1988 witnesses. The Spruce SE is in good condition. The other two BTs are dead and down. The
monument was found to be substantially at the record position and is accepted as a careful and
faithful establishment of the position of the corner.

(10-Sec. 31) Established the position for the corner midway and on the Range Line between Township
corner 1306.82' south and Quarter corner 1306.82' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Found 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
12" Spruce S39°E 30.7' old blaze (1988 BT)
6" Balsam N70°E 13.65' mrkd "1/16S BT"
6" Tamarack S54°W 8.0' do
4" Cherry N02°W 14.9' do
Set sq'd spruce post adjacent.
E= 7896892.350 N= 202388.252

(10) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Maple N74°E 17.15' mrkd "1/16S BT"
7" Sugar S18°E 23.7' do
18" W.Pine S42°W 29.4' do
10" Spruce N23°W 19.0' do
Set sq'd cedar post adjacent.
E= 7895366.298 N= 202418.652

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 data
Coord. Ref.=NGS PID RL1468: N= 199449.725 m. E= 7900599.998 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 03/18/2016

For the Michigan Department of Natural Resources, Forest Resources Division

