

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 49N R 32W

C6

T 49N R 32W

F4

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

F4 Jun 12 2002

C6 Jun 11 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8					10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17 & 18. 1852: Established by Guy H. Carleton. "South corrected...40.00 Set quarter post. Sugar 18 N75E 10 links, Maple 7 S23W 22 links". Found no subsequent record. The Baraga Co. engineer at the County Rd. Commission told me that he has no information pertaining to this corner.

(F4) Center of Section 9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) The original post and accessories were not recovered. Remains of the BTs would likely have been removed during construction of Torvinen Road, the centerline of which crosses the section line 18' south of the position subsequently monumented. I reestablished the corner equidistant between Section corners 2628.9' north and south and in an old N-S fence line which runs along the east side of a spruce plantation in Sec. 18. The fence is very old, the posts have rotted and it is all down on the ground. It runs to the north only. No fencing was found south of the road. Champion International foresters have been using one of the old rotted fence posts about 14' north of the corner monumented for an approximate corner. The reestablished corner is 31.2' East of a straight line between section corners.

(F4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the

(C6) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Blazed and scribed:
10" Sugar N17E 10.6' "1/4S NBT"
9" Hemlock S83E 35.1' do
8" Maple S27W 34.7' do
5" Y.Birch N82W 1.1' do
Squared cedar post adjacent. Bearings
are magnetic. Distances are to notch in
lower blaze.

(F4) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Blazed and scribed:
8" Sugar N23E 12.2' "C1/4 BT"
10" Sugar N69E 14.1' do
8" Sugar S70E 10.6' do
12" Y. Birch S86W 13.7' do
Set squared cedar post adjacent.
Bearings are magnetic. Distances are to
notch in lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 7/11/02

For the Michigan Department of Natural Resources - Office of Property Management

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995