

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 34W	C10
	T R	
2. Property Controlling in Section	S 29 T 49N R 34W	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 10/15/12 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C10) **Quarter corner common to Sections 29 and 30.** 1959 - Billy D. Buckler RLS reestablished the corner position by proportionate measurement between Section corners. Set 1" iron pipe with 4" brass cap. 6" J.Pine N66W 04 links, 6" J.Pine S86E 11.5 links.

(10-Sec. 29) **South 1/16 corner between Sections 29 and 30.** Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C10) Found the 1959 monument in good condition and substantially at the record position. No definitive remains of the 1959 NBTs was recovered. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(10-Sec. 29) Established the position for the corner midway and on the Section line between Section corner 1307.90' south and Quarter corner 1307.90' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C10) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
6" J.Pine N03°E 11.85' mrkd "1/4S NBT"
7" J.Pine N64°E 21.65' do
6" J.Pine S29°W 15.55' do
5" J.Pine N85°W 16.6' do
Sq'd a 6" J.Pine stub, adjacent.
E=7877813.486 N=204781.746

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
4" J.Pine N49°E 26.6' mrkd "1/16S BT"
6" J.Pine S70°E 8.7' do
6" J.Pine S17°E 29.75' do
4" J.Pine N62°W 5.7' do
4"x4" treated post adjacent to the north
E=7877803.029 N=204383.290

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 03/13/2013

For the Michigan Department of Natural Resources, Forest Resources Division

