

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 30W	C4
	T R	
	T R	
2. Property Controlling in Section	S 8 T 51N R 30W	12
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7	8			9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 08/19/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C4) Quarter corner common to Sections 7 and 8. 1846 - Established by Hubbard and Ives, Deputy Surveyors, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Sugar 5" S83°E 12 links, Hemlock 13" N40°W 29 links. Found no subsequent record.

(12-Sec. 8) South 1/16 corner, Section 8. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C4) The original post and accessories were not recovered. Found no monumentation at the corner position. From the position subsequently monumented, I found a 22" Y.Birch signature tree dating to the 1960's, blazes on the west side, 30 ft. east and 27 ft. north, which I did not accept as evidence of the position of the original corner, it being too far from the original record position and probably marking an approximate forestry corner. Established the position for the corner midway and on the Section line between Section corner 2659.84' north and south.

(12-Sec. 8) Established the position for the corner midway and on a straight line between Quarter corner 1319.68' south and Center of Section 8 1319.68' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C4) Set 1"IDx28" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
7" Maple S29°E 17.7' mrkd "1/4S NBT"
9" Hemlock S25°W 29.9' do
18" Cedar West 28.4' do
7" Maple N09°W 7.95' do
Set sq'd cedar post adjacent.
E= 7912253.503 N= 228139.939

(12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
4" Sugar N09°E 21.15' mrkd "1/16S BT"
13" Hemlock N78°E 27.8' do
6" Sugar S07°W 28.05' do
5" Sugar N49°W 10.6' do
Set sq'd cedar post adjacent.
E= 7913046.057 N= 227726.090

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.169 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/08/2013

For the Michigan Department of Natural Resources, Forest Resources Division

