

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 31W T 51N R 31W T S T R S T R S T R S T R	M2 L3
2. Property Controlling in Section		
3. Miscellaneous Property in Sec.		
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/10/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M2) Quarter corner common to Section 1 T51N-R31W and Section 6 T51N-R30W. 1845 - Established by Wm. Burt on the Range line between Section corner 40.00 chains south and Township corner 38.85 chains north. Set post. 10" Hemlock S11°W 32 links, 16" Hemlock N58°W 31 links. Found no subsequent record.

(L3) Quarter corner common to Sections 1 and 12. 1846 - Established by Hubbard and Ives, Deputy Surveyors, midway and on the Section line between Section corners 40.12 chains east and west. Set post. Spruce 10" S03°E 11 links, fir 4" N39°W 19 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M2) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on the Range line between Section corner 2634.48' south and Township corner 2558.75' north, being proportionate to the original record. Determined the true bearing of the Range line to be N0°00'38"W on this mile.

(L3) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the position for the corner on the Section line between Section corners 2656.87' east and west, proportionate to the original record. From the position thus established, the physical center of Roland Lake Road is 8 ft. east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M2) Set 1"IDx32" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
16" Y.Birch N21°E 9.05' mrkd "1/4S NBT"
14" Cedar S20°E 30.9' do
12" Cedar S20°W 17.5' do
18" Hemlock S83°W 5.05' do
Set sq'd cedar post adjacent.
E= 7910655.942 N= 229777.607

(L3) Set 1"IDx32" I.pipe with 2" alum. MDNR cap 5" below the surface of Roland Lake Road. Set measuring nail with MDNR tag in the side of:
15" Cedar N55°E 62.1' mrkd "1/4S NBT"
9" W.Spruce S51°E 58.2' do
7" Y.Birch West 19.7' do
9" Cedar N80°W 53.5' do
Center of Road, East 8 ft.
E= 7909834.585 N= 228987.865

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

