

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 51N R 31W

T 51N R 32W

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Section

S T R

A-13

M-13

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
599 - 600.

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, Michael Mileski, in a field survey on December, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13, M-13; Section Corner common to Section 31, T51N, R31W and Section 36, T51N, R32W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990

Baraga County

12-19-95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13, M-13; Section Corner common to Section 31, T51N, R31W and Section 36, T51N, R32W, on 5th Correction Line.

Found Mr. Thompson's cedar post in reasonable agreement with his remaining new bearing tree the condition of which is described in Part A. During the course of the retracement survey a 1/2" x 18" iron rod and cap #39091 was set at the north side of Mr. Thompson's post for use as a control point. I reestablished the corner at proportionate distance along a latitudinal curve between the southwest corner of Section 35, T51N, R32W and the south one-quarter corner of Section 31, T51N, R31W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13, M-13; Section Corner common to Section 31, T51N, R31W and Section 36, T51N, R32W, on 5th Correction Line.

See back of form.

Signed by

Michael Mileski

Date

28 Dec 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983



A. Description of original monument and accessories and/or subsequent restoration:

A-13, M-13; Section Corner common to Section 31, T51N, R31W and Section 36, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Maple 16 N16°E 23 lks. (Gone)

and a

Lynn 16 N62°W 10 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes dated 2 December 1941 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he "ch. from ¼, W. 42.00 chains, set cor., set ced. post", Mr. Thompson noted the following new bearing trees:

Sugar 18 N55°E 32'8"
(Recovered as a severely decayed stump.)

and a

Hemlock 16 N15°W 9'10"
(Destroyed by logging operations.)

Mr. Thompson's monument was not accepted during the course of a survey conducted by Michael Avery and Stephen Douglas of the Bureau of Land Management from 17 September 1982 to 30 September 1983 and approved 8 July 1985. The BLM considered this corner lost, but did not remonument it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13, M-13; Section Corner common to Section 31, T51N, R31W and Section 36, T51N, R32W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	N/side	14" Hemlock	N60°E	57.35'
Set 60d spike	SW/side	14" Hemlock	S44°E	44.70'
Set 60d spike	W/side	24" Hemlock	S12°W	38.42'
Set 60d spike	S/side	12" Cedar	N74°W	26.75'

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".