

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 33 T 51N R 34W	2
	S 28 T 51N R 34W	13
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 13 06/05/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 33) East 1/16 corner common to Sections 28 and 33. 1978 - K.L.Sackett RLS set a 1"ID x36" I.pipe to mark the corner position and made the following witnesses: 9" Cedar S13°E 20.2', 6" Cedar N16°E 47.4', 9" Sugar N83°W 31.2'.

(13-Sec. 28) Southeast 1/16 corner, Section 28. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 33) Found the 1978 monument in good condition and at record bearing and distance from two 1978 witnesses, but found the monument position to be N56W 39.6' from the position subsequently monumented, presumably because the 1978 position for Quarter corner F11 does not conform to the position established and approved by the Baraga County Remonumentation Program in 2002. I accepted the Baraga County monumentation as controlling and reestablished the position for this corner midway and on the Section line between Quarter corner F11 1260.58' west and Section corner G11 1260.58' east. Removed the 1978 monument and left it adjacent to the reestablished position.

(13-Sec. 28) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
13" Sugar N20°E 28.0' mrkd "1/16S BT"
4" Sugar N82°E 24.0' do
17" Sugar South 18.2' do
14" Cedar N81°W 27.05' do
Set sq'd cedar post adjacent.
E= 7876201.781 N= 223152.844

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" Spruce N27°E 30.8' mrkd "1/16S BT"
6" Cedar S10°E 72.4' do
4" Spruce N84°W 27.5' do
6" Cedar N33°W 21.0' do
Set sq'd cedar post adjacent. C/L of dirt road is approx. 23' south.
E= 7876211.874 N= 223550.436

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID RL0593: N= 221669.506 m. E= 7868965.488 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/01/2013

For the Michigan Department of Natural Resources, Forest Resources Division

