

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 30W	I10
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 04/19/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I10) Quarter corner common to Sections 26-27. 1846 - Established by Wm. Ives Deputy Surveyor midway
and on the Section line between Section corners 40.00 chains north and south. Set post. Hemlock 10"
N75E 15 links, Y.Birch 15" N66W 24 links. 1940 - Notes of Norman T. Thompson RLS state: "run N. from
SW cor [of Sec. 26] V.0 hit Bir. 20" line tree, hit 6 ft. West of 1/4. B.T. Hem. down, just a slab.
A 22" Bir. B.T. Set bal. post according to Hem....continued N. V.0 hit 6 ft. east" [of Section
corner I9].

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I10) The original post and accessories were not recovered. Found a 3/4" ID I.pipe and markings on a
15" Hemlock S77W facing, overgrown upper and lower blazes. The position for the corner is 4.3' south
of a point equidistant between Section corners and is 13' east of a straight line between them. The
position is substantially in accord with the offsets noted in the Thompson record. I accept the pipe
as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap,
driving it over the found 3/4" iron pipe.
Set measuring nail with MDNR tag in the side of:
7" Y.Birch N08E 9.1' mrkd "1/4S NBT"
6" Maple S13E 12.15' do
15" Hemlock S77W 24.0' do
6" Sugar N32W 3.3' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 05/18/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities