

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 30W	K9
	T 52N R 30W	J9
	T	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on K9 04/14/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. 1846 - Established by Wm. Ives Deputy Surveyor. Set  
post. Cedar 10" S47W 27 links, Hemlock 17" N86E 17 links. Found no subsequent record.

(J9) Quarter corner common to Sections 23-26. 1846 - Established by Wm. Ives Deputy Surveyor midway  
and on the Section line between Section corners 40.09 chains east and west. Set post. Y.Birch 10"  
N11E 19 links, B.Ash 14" S22W 12 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) The original post and accessories were not recovered. Found a 3/4" ID I.pipe with old Ford  
Motor Co. location poster, affixed to a 14" Hemlock S25W, facing. The position for the corner fits  
well with corners recovered 1/2 and 1 mile west and 1 mile south. I accept the pipe as the best  
available evidence of the position of the original corner. Placed a new monument at the position of  
the pipe.

(J9) Found a 1" ID iron pipe at record bearing and distance from the remains of the Y.Birch BT N11E  
19 links, now dead and down, with scribed face visible. Accepted the pipe as a careful and faithful  
perpetuation of the position of the original corner. The pipe is 5.1' east of a position equidistant  
between Section corners and 2.5' north of a straight line between them. An old Ford Motor Co.  
location poster was found on the Cedar NBT, below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
13" Hemlock N82E 32.0' mrkd "S24 NBT"  
11" Maple S33E 22.3' "S25 NBT"  
14" Hemlock S25W 22.85' "S26 NBT"  
9" twin Maple N15W 11.8' "S23 NBT"  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

(J9) Fd. 1"ID I.pipe. Inserted plastic MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
8" Ash N41E 3.15' mrkd "1/4S NBT"  
9" Maple S75E 12.6' do  
9" Sugar S80E 2.2' do  
11" Cedar N20W 20.25' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 05/18/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities

