

# SURVEY & REMONUMENTATION

APR 08 1996

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

DEC 14 1 33 PM '95

For corners of COMMISSION

Sandy Schindelmayr  
REGISTER OF DEEDS

002334

Register of Deeds Stamp & File Number

Barry  
(County)

Located In: Corner Code #

1. Public Land Survey T 2N R 9W E-7  
Southwest corner of T R  
Section 16, Hope Township T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. , Recorded Plat  
5. Private Claims

I, Kenneth C. Brandt, in a field survey on December 1, 19 95,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A Yellow Oak 7" S. 47° W 61.  
DO. 7" S. 44° E 91.

By: Sylvester Sibley D.S.  
1827 (R9W P. 81-82)

County Surveyor Heath found plow point in line of old fence for corner (TAN Hope Twp.  
F.B., P.15

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" solid iron stake 4' W of West edge of limestone drive in harmony with Plat of  
Long View Point - (L. 3 of Plats, Page 95) by William Hume Rogers R:S# 6197 - Referenced -  
No witnesses 7/10/54. ALSO in harmony with Colvin's Plat (L.4 of Plats, Page 59) by Robert  
H. Gove P.E. & RLS. #7944 2/2/62. Referenced - no witnesses.  
No witnesses found this date.


ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
JULY 10, 1995 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Barry County Remonumentation Monument (3/4" x 36" Rod W/Aluminum Cap)

Witnesses:

Nail & Barry County Shiner - E Side 48" Black Oak S.25° W. 12.83 feet.  
Nail & Barry County Shiner E. Side 28" White Oak N.15° W. 36.61 feet.  
Nail & Barry County Shiner - S. Side 30" Black Oak S.55° E. 76.91 feet.  
Nail & Barry County Shiner - S Side 18" Black Oak N.45° E. 96.25 feet.



Signed by Kenneth C. Brandt

Date 12/12/95

Surveyor's Michigan License No. 24587